

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 48NR 41W	D-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REMONUMENTATION

OCT 8 0 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 20 & 29, T48N R41W.

I, Earl W. Applekamp, in a field survey on Aug. 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Wells Burt, U.S. Deputy Surveyor, June 14, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

14"	Cedar	N50°W	12.12 feet
30"	W. Pine	S15°W	13.86 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. Apparent corner falls in the centerline of an East-West County blacktop road. Farming has been active on both sides of road for 70 plus years. I re-established the corner by single proportionate measure between opposite section corners East & West and in the centerline of the blacktop road. There is a woods field line near this position running both North and South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x8" rebar with a stamped 3" cap 2" below top of blacktop road. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, R.M., 1/4, S20, S29, 1997, P.S. 17610. I also established three other bearing objects.

REF MON	S15°-12'-26"W	54.26'	- 6" Aspen	N18°-43'-02"E	81.65'
Power Pole	N77°-38'-30"W	160.40'	- Power Pole	N79°-50'-35"E	190.34'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 15, 1997