

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEMM
 Ontonagon County

Page 1 of 1
 REC'D Date 10/27/1999 Time 12:50:11
 RECORDING FEE: 2.00

For corners in

ONTONAGON
 (County)
GOGEBIC

Located In:

Corner Code #

1. Public Land Survey

T48NR 41W	D-13
T47NR 41W	D-1
T___R___	_____
T___R___	_____
S___T___R___	_____
S___T___R___	_____
S___T___R___	_____
S___T___R___	_____

2. Property Controlling
 in Section

3. Miscellaneous
 Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner common to Sections 5 & 32, T47 - 48N, R41W.

I, Earl W. Applekamp, in a field survey on Oct. 01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**SURVEY &
 REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4			3		2		
3													
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by William A. Burt, U.S. Deputy Surveyor in 1847. ORIGINAL BEARING TREES: Hemlock 8" N39°E 18 Links, Cedar 6" N59°W 12 Links. In 1970 Donald Lappala RLS 12585 restored the corner from an 11" Cedar windfall with a GLO blaze and other GLO evidence. He set a 2 1/2"x5' long concrete filled galvanized pipe capped with a 3" bronze tablet, which reads, T47-48N R41W, 1/4, S-5, S-32, RLS 12585, 1970. He established 3 bearing trees, 6" Red Maple N20°E 113.6 feet, 3" Red Maple N77°E 105.6 feet, 8" Aspen S86°E 122.4 feet. A Corner Certificate was recorded in Book #2, Page 2-7, Ontonagon County Records, September 14, 1972.

DEED GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 10-14-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In September of 1999 I recovered the corner set by Donald Lappala. It was under water in a beaver pond. It required draining of the pond in order to survey its location. The monument was in good condition. I found one of Lappala's bearing trees, the 3" Red Maple which has been dead for several years. I set a 6' Steel Sign Post at the corner location and established a Witness Corner on the Section Line East of the corner as shown below.



Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I established a Witness Corner, a 2 1/2"x30" split base aluminum pipe with a 3" cap S89°-42'-31"E, 147.42 feet from the corner and on the South line of the Section. The cap is stamped to read: County Remonumentation, T47N, T48N, R41W, 1/4, S5, S32, W.C., 1999, P.S. 17610. The bearing and distance from the corner is also stamped on the cap. I established 3 bearing trees and a reference object, to the Witness Corner.

Nail in 6" Aspen	N25°E	61.86'	-	Nail in 5" H. Maple	S46°E	60.07'
Nail in 5" Aspen	N70°E	46.15'	-	6' Steel Sign Post	West	0.63'

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 6, 1999