

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. <u>Public Land Survey</u>	T <u>48NR 41W</u>	<u>E-6</u>
	T <u> R </u>	<u> </u>
	T <u> R </u>	<u> </u>
	T <u> R </u>	<u> </u>
2. <u>Property Controlling</u> <u>in Section</u>	S <u> T R </u>	<u> </u>
	S <u> T R </u>	<u> </u>
3. <u>Miscellaneous</u> <u>Property in Sec.</u>	S <u> T R </u>	<u> </u>
	S <u> T R </u>	<u> </u>

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 16 & 17, T48N R41W.

I, Earl W. Applekamp, in a field survey on Nov. 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 13, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

40" White Pine	S88°W	9.24 feet
10" Sugar Maple	S85°E	14.52 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was re-established by single proportionate measure between opposite section corners. Corner position fell on a down woven wire fence. No fence could be found running West, which is a property division line.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 11-11-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" split ^{BASF} aluminum monument with a 3" cap stamped to read: County Remonumentation, T48N R41W, S16, S17, $\frac{1}{4}$, 1997, P.S. 17610. I established 3 bearing trees and a reference object.

5" Aspen	S22°W	21.73 feet	-	9" Spruce	S42°E	32.20 feet
6" Aspen	N06°E	43.19 feet	-	Steel Sign Post	West,	0.90 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date November 8, 1997