

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R 41W	E-10
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**SURVEY &
 REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 28 & 29, T48N R41W.

I, Earl W. Applekamp, in a field survey on Oct. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 1851. Set Wood Post.

ORIGINAL BEARING TREES:

16" Sugar S67°W 15 Links (9.90 Feet)
 18" W. Pine N45°E 8 Links (5.28 Feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original or subsequent evidence was found. Corner was re-established by single proportionate measure between opposite corners North & South. This position is in agreement with the original field note call to the Ten Mile Creek, 1.61 Chains South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp 11-09-99
 COUNTY REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, R41W, $\frac{1}{4}$, S28, S29, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 6" Aspen N70°W 56.26' - Nail in 6" Aspen N84°E 50.12'
 Nail in 5" W. Birch N02°W 124.83' - 6' Steel Sign Post South 0.64'



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date October 21, 1999