

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
(County)

Located in:

Corner Code #

1. Public Land Survey

T48NR 41W

F-7

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

REGISTERED
REMONUMENTATION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

1/4 Corner common to Sections 16 & 21, T48N R41W.

I, Earl W. Applekamp, in a field survey on July 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 7.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 10, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

10" Maple N36°W 5.28 feet
10" Yellow Birch S15°E 12.54 feet

PEER GROUP APPROVAL
Earl W. Applekamp
COUNTY REGISTERED
8-19-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Near the corner position I found a wood stake laying on the ground. A forester had marked a line South from this position several years ago. I re-established the corner by single proportionate measure between opposite section corners East and West. Corner location is in agreement with GLO creek calls.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, 1/4, S16, S21, 1998, P.S. 17610. I established three bearing trees and a reference object.

Nail in 6" Balsam S41°W 14.84' - Nail in 4 1/2" Spruce N72°E 17.15'
Nail in 9" Balsam N07°W 35.38' - 6' Steel Sign Post North 0.74'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date August 17, 1998