

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>41W</u>	<u>F-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
 OCT 30 1997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner common to Sections 21 & 28, T48N R41W.

I, Earl W. Applekamp, in a field survey on Aug. 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 16, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

8" Maple S18°W 10.56 feet
 14" Spruce East 9.90 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Apparent corner position falls in a county blacktop road running East & West. There is no farming or grazing activity in the area. Corner was re-established by single proportionate measure between opposite section corners East & West and in the centerline of the blacktop road. A 1" pipe was found at 32 feet South of where I set the corner. No record of who or when this was set.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x8" rebar with a 3" stamped cap 1" below top of blacktop. I established a reference monument, a 2½"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, R.M., ¼, S21, S28, 1997, P.S. 17610. I also established three other bearing objects.

REF MON S00°-56'-56"W 37.90' - Power Pole N66°-12'-31"W 64.47'
 7" Aspen S46°-00'-26"W 65.69' - 5½" Spruce N51°-49'-02"E 77.42'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 15, 1997