

LAND CORNER RECORDATION CERTIFICATE Date 11/12/1999 Time 16:14:17

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 41W	F-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY &
 REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 28 & 33, T48N R41W.

I, Earl W. Applekamp, in a field survey on Oct. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 1851. Set Wood Post.

ORIGINAL BEARING TREES:

- 12" Cedar N76°W 17 Links (11.22 feet)
- 10" Cedar S58°E 21 Links (13.86 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Area has been disturbed for construction of a private road. Corner was re-established by single proportionate measure between corners East and West and in the center of the private road.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp 11-09-99
COURT RECONSTITUTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" cap 4" below top of gravel and wood chip road. Cap is stamped to read: County Remonumentation, T48N R41W, 1/4, S28, S33, 1999, P.S. 17610. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped as above. I also established three bearing trees.

- Nail in 8" Spruce N57°W 60.02' - Nail in 3" Aspen S33°E 34.12'
- Nail in 7" Spruce N24°E 25.42' - REF. MON. S01°W 21.31'

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 23, 1999