

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N R 41W</u>	<u>G-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

OCT 9 9 1997

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner common to Sections 15, 16, 21 & 22, T48N R41W.

I, Earl W. Applekamp, in a field survey on Aug. 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 10, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

30" W. Pine	N70°W	7.92 feet
10" Elm	N55°E	9.90 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the apparent corner position there is a well maintained fence running North & East with cattle being pastured. These fences have been in this position since about 1910. I re-established the corner at this position as being the only logical position for the corner. The position is in agreement with the original GLO calls.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" split aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, S15, S16, S21, S22, 1997, P.S. 17610. I also established three bearing trees and a reference object.

7 1/2" Aspen	S82°W	23.22'	-	9" Aspen	S66°E	25.38'
8" Aspen	N24°W	21.22'	-	Steel Sign Post,	South	0.90'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date September 16, 1997