

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>41W</u>	<u>G-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED
OFFICE OF THE REGISTER
OCT 30 1997
GONIA
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner common to Sections 21, 22, 27 & 28, T48N R41W.

I, Earl W. Applekamp, in a field survey on April 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Deputy Surveyor, June 1851. Set Post.

ORIGINAL BEARING TREES:

Spruce 12" N20°W 25.74 feet
Fir 12" S48°E 21.78 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls in the intersection of a "T" road running East-West and South. Distance to opposite section corners is in agreement with the original survey distance. I re-established the corner at the intersection of the roads as being the only logical corner position.

Research on file with the County Remonumentation Representative.

FEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X24" rebar with a 3" cap 2" below top of blacktop. I set a reference monument, a 2 1/2" aluminum pipe with a 3" cap stamped to read: T48N R41W, R.M., S21, S22, S27, S28, 1997, P.S. 17610. I established 3 other bearing objects.

REF. MON. N28°E 40.70' - Power Pole S46°W 51.35'
Fence Post S33°E 46.41' 4" Aspen N40°30'W 85.22'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date April 28, 1997