

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 41W

H-7

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

REGISTERED
REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 7.

1/4 Corner common to Sections 15 & 22, T48N R41W.

I, Earl W. Applekamp, in a field survey on July 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Wells Burt, U.S. Deputy Surveyor, May 25, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

10" Fir N12°W 7.26 feet
8" W. Birch S57°E 15.84 feet

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REGISTER
8-19-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. The land North and West is a field and has been farmed since the 1920's and is still active. The land North and West of the corner is fenced. The calculated position is about 17 feet East of the existing fence corner. I re-established the corner at the existing fence corner as being the only logical position of the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, 1/4, S15, S22, 1998, P.S. 17610. I established 3 bearing trees and a reference object.



Nail in 19" W. Pine S35°W 74.99' - Nail in 20" Tamarack N40°E 46.73'
Nail in 15" Aspen S71°W 46.17' - 6' Steel Sign Post West 0.88'

Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date August 17, 1998