

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>41W</u>	<u>I-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REMO
 OCT 8 1997
 COMMISS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner common to Sections 14 & 15, T48N R41W.

I, Earl W. Applekamp, in a field survey on May 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Deputy Surveyor, May 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Spruce 12" N24°E 3.96 feet
 Maple 10" S62°W 7.92 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position I found a 1/2" Iron Pin 12" below top of a gravel road. The distance from this position to the corner South is in agreement with the original field notes. This position is at a "T" road with roads running East, West & South. These roads have been in existence since about 1910. I accepted the 1/2" Iron Pin as the true position and established the monument described in "C".

Research on file with the County Remonumentation Representative.

BEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 5-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" Rebar with a 3" stamped aluminum cap 6" below the gravel. I set a reference monument, a 2 1/4"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, 1/4, T48N R41W, R.M., S14, S15, 1997, P.S. 17610. I established 3 other witness objects.

REF. MON. S27°W 47.69' - Power Pole N42°E 42.87'
 6" Spruce N04°W 39.17' - 20" W. Pine S37°E 142.85'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date May 8, 1997

257