

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 41W	I-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED  
 OCT 3 0 1997  
 COMMISSION  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 22, 23, 26 & 27, T48N R41W.

I, Earl W. Applekamp, in a field survey on April 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9									●				
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Deputy Surveyor, June 1851, set Post.

ORIGINAL BEARING TREES:

W. Pine 20" S35°E 9.90 feet  
 Spruce 16" N70°W 15.84 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

There is no evidence of original bearing trees. At the corner position there is a "T" road running East-West and North. A dirt road runs South from the corner position. Distance to opposite corners are in agreement with original. I re-established the corner at the intersection of the roads as being the only logical corner position.

Research on file with the County Remonumentation Representative.

PEER GROUP APPROVED  
Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 5-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3" cap 2" below top of blacktop. I established a reference monument, a 2 1/2" aluminum pipe with a 3" cap stamped to read: T48N R41W, R.M., S22, S23, S26, S27, 1997, P.S. 17610. I established 3 other bearing objects.

Ref. Mon. N44°W 58.43' P.Pole S44°E 47.54'  
 6" Aspen N54-30E 65.23' Tel. Box Post S46°W 42.80'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date April 26, 1997