

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R41W	K-5
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

COUNTY OF ONTONAGON
 REGISTER OF DEEDS
 JAN 11 1998
 SECTION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 11, 12, 13 & 14, T48N R41W.

I, Earl W. Applekamp, in a field survey on June 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 19, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

18" Sugar Maple S38°W 15.84 feet
 60" White Pine N60°W 15.18 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTER 8-19-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the calculated position there was some fence wire on the ground in the vicinity. No fence posts were found. I re-established the corner by extending the line from the Section and ¼ Corner to the East and using the measurement between these two corners. This position is in conformance with GLO calls to corners East, West and South.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, S11, S12, S13, S14, 1998, P.S. 17610. I established the following bearing objects.

Nail in 6½" Maple S69°W 48.21' - Nail in 9" Maple S48°E 28.66'
 Nail in 6" Maple N37°W 45.24' - 6' Steel Sign Post East 1.09'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 16, 1998