

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 41W</u>	<u>K-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SECTION
 FILE NO. 17610

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Section Corner common to Sections 13, & 14, T48N R41W.

I, Earl W. Applekamp, in a field survey on June 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by wells Burt, U.S. Deputy Surveyor, June 20, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

14" Spruce	N74°E	8.58 feet
12" Maple	S75°W	10.56 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY SURVEYOR
 7-22-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position is in a County Road running East and West. I found a $\frac{1}{2}$ " iron pin in the centerline of the County Road, which has been used for surveys in the area. This position is in agreement with an occupied line North & South. I accepted the $\frac{1}{2}$ " iron pin and replaced it with a monument described below in "C".

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" stamped cap 6" below top of the gravel road. Cap is stamped to read: County Remonumentation, T48N R41W, $\frac{1}{4}$, S13, S14, 1998, P.S. 17610. I established a reference monument which is a 2 $\frac{1}{2}$ "x30" split base aluminum pipe with a 3" cap stamped as above. I also established 3 other bearing objects.

REF. MON. N00°-47'-49"W 33.61' - Nail in Pwr. Pole S83°E 226.58'
 Nail in 14" Oak N10°W 114.39' - Nail in Pwr. Pole S07°W 33.29'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 15, 1998