

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
 (County)

Located In:

Corner Code #

1. Public Land Survey

T48N R41W K-9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REGISTERED
 JAN 11 1998
 SECTION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

Section _____

Corner common to Sections 23, 24, 25 & 26, T48N R41W.

I, Earl W. Applekamp, in a field survey on June 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 21, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

30" W. Pine N68°E 16.50 feet
 12" Y. Birch N63°W 4.62 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY SURVEYOR
 7-22-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

No original evidence was found. Corner falls in Old Highway M-28 which has been in existence since about 1920. I found a 1/2" iron pin in the center-line of the road at the corner position. This iron pin was used for several surveys by E.W. Applekamp, P.S. # 17610 in 1984 and later. This position is in conformance with the original field notes calling a stream East of the corner. I accepted the 1/2" iron pin and monumented the corner as described in "c".

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

At the corner position I set a 3" cap on the 1/2" iron pin 3" below the top of blacktop. The cap was stamped to read: County Remonumentation, T48N R41W, S23, S24, S25, S26, 1998, P.S. 17610. I established a reference monument which is a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped as shown above. I also established 3 other bearing objects.

REF. MON. N01°-03'-38"W 34.15' - Power Pole S86°E 441.15'
 13" Spruce N72°W 376.58' - Power Pole S71°E 94.84'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 25, 1998