

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>ONTONAGON</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>48</u> R <u>41</u>	K-11	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Recorded December 19 1994
at 2:30 o'clock P. M. in
Liber Survey 3 page 251
Julie Bailey deputy
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner 25, 26, 35 & 36, T48N R41W

I, Earl W. Applekamp in a field survey on December 10, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Deputy Surveyor, June 1857. Set Wood Post.

Original Bearing Trees:

W. Birch	12"	N67°W	14 Links	(9.24 feet)
Cedar	10"	N27°E	8 Links	(5.28 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No physical evidence of the corner was found, except two creek crossings.

Corner was set using the calls to the two creek crossings North and West and a creek crossing to the South.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/4" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, S.25, S.26, S.35, S.36, T48N R41W, 1994, P.S. 17610. I established the following trees and reference objects.

8" Poplar	N78°W	37.10 feet	-	Steel Sign Post North 1.71 feet
6" Poplar	N35°E	34.35 feet		
10" Poplar	S28°E	44.00 feet		



Signed by Earl W. Applekamp Date December 12, 1994
Surveyor's Michigan License No. 17610

251