

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R41W	L-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

JAN 11 1998

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

$\frac{1}{4}$ Corner common to Sections 24 & 25, T48N R41W.

I, Earl W. Applekamp, in a field survey on June 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 21, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

40" W. Pine S05°E 1.98 feet
 6" Spruce N04°W 7.26 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 7-22-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No original evidence was found. Corner location is on the Old M-28 roadway which has been in existence since 1920. Corner was re-established by single proportionate measure between Section corners East & West and in the center-line of the blacktop road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" stamped cap 2" below top of blacktop. Cap is stamped to read: County Remonumentation, T48N R41W, $\frac{1}{4}$, S24, S25, 1998, P.S. 17610. I established a reference monument which is a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped as above. I also established 3 other reference objects.

REF. MON. Due South 39.57' - Nail in 6" Aspen N62°W 74.05'
 Nail in Power Pole, S78°W 153.29' - Nail in 8" Aspen N17°E 71.50'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 25, 1998