

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 40W T48N R 41W T___ R___ T___ R___	A-9 M-9
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____ _____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____ _____

SURVEY &
 REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 19 & 30, T48N R40W and
 Sections 24 & 25, T48N R41W.

I, Earl W. Applekamp, in a field survey on June 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, July 16, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

8" Spruce N11°E 9.24 feet
 8" Cedar N11°W 9.90 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY SURVEYOR
 7-22-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner is marked by a R.R. Spike in the blacktop at the center-line of a blacktop road running East & West and a gravel road running North. This road has been in existence since about 1915. The R.R. Spike has been used to describe several parcels of land in the area. I accepted the R.R. Spike as being the location of the original corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I replaced the R.R. Spike with a 5/8"X12" rebar with a 3" cap 2" below top of blacktop. The cap is stamped to read: County Remonumentation, T48N R40W, R41W, S19, S30, S24, S25, 1998, P.S. 17610. I established a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read the same as above. I also established 3 bearing trees.

REF. MON. N43°-56'-28"E 66.41' - Nail in 10" Scotch Pine S01°E 51.12'
 Nail in 11" Scotch Pine S39°E 77.37' - Nail in 7" Aspen N32°W 80.23'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 20, 1998