APR 2 9 1998

JUDITH D. ROEHM Ontonagon County

3/ 377 MEL

10/26/95

14:11

ee: 9,00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Page 1

Filing Requirement of Act 74, Mich. P.A. 1970

ONTONAGON Located In: Corner Code # 7...48_ R <u>4</u>2 1. Public Land Survey R 43 48 49 42 A-13 T R R 43 49 M-13Т 2. Property Controlling Т R in Section Т 3. Miscellaneous Property in Section

Register of Deeds Stamp & File Number


4. Lot No. , Recorded Plat

T48N R43W, T49N R42W & T49N R43W.

5. Private Claims Section Corner common to Sections 1, 6, 31, & 36, T48N R42W,

I, Earl W. Applekamp, in a field survey on August 2 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



Original Corner established by William A. Burt, U.S. Deputy Surveyor, August 14, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Sugar 16" S40°E 11 links (7.26 feet) Sugar 12" N63°W 54 links (35.64 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence of post or bearing trees were found. A stream call on the original notes 640 feet North of corner, agrees with the location of the re-established corner. The corner was re-established at the latitude of the Section Corner 1 mile East and a $\frac{1}{4}$ Corner $\frac{1}{2}$ mile West. Departure of the corner was set at a proportional distance using the same two corners. Total distance differed by 15 feet compared to original notes. I established the monument described in "C" below.

Research on file with County Remonumentation

Program Representative.

COUNTY BEPRÉSENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a $2\frac{1}{2}$ "x30" aluminum pipe with a $3\frac{1}{4}$ " cap stamped to read: T48N R42W, T48N R43W, T49N R42W, T49N R43W, S1, S6, S31, S36, 1995 STATE OF MICHIGAN P.S. 17610. I established the following bearing trees and steel post.

4" Ironwood 10" Oak

S40°W N53°E 15.00 feet 41.95 feet

6" Maple Steel Sign Post North

S71°E

25.35 feet.

MIC, ら、EARI な。 1.60 fee **APPLEKAMP PROFESSIONAL**

SURVEYOR

Surveyor's Michigan License No.

Date September 21, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. REVISED MAY 14, 1975 **REVISED JAN., 1983**