

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 3/375 MEL Fee: 9.00
 10/26/95
 14:11
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONOTNAGON
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>48</u>	R	<u>42</u>	<u>A-2</u> ✓
	T	<u>48</u>	R	<u>43</u>	<u>M-2</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 1 & 6, T48N R42W & T48N R43W

I, Earl W. Applekamp in a field survey on August 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt, U.S. Deputy Surveyor, August 13, 1848. Set Hemlock Post.

ORIGINAL BEARING TREES:

Black Oak	20"	S71°E	9 Links	5.94 Feet
Hemlock	8"	N37°W	24 Links	15.84 Feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a squared wood stake set in a pile of rocks. Blazed lines went North and West from this position. The original notes called a ledge 5 chains South, which was in agreement. A top of the hill call 3.50 chains North was also in agreement. A miners home 3 chains East was not found.

I restored the corner at the stake and pile of rocks, as this location was consistent with the original calls. I set a monument and ties as described in "C" below.

Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp 10-18-95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" aluminum pipe with a 3¼" cap stamped to read: COUNTY REMONUMENTATION, T48N R42W, R43W, $\frac{1}{4}$, S1, S6, 1995, P.S. 17610. I established the following bearing trees and reference objects:

10" Oak	N26°W	23.15 Feet	-	Steel sign post South,	2.30 Feet
6" Maple	S81°W	23.79 Feet	-	6" White Birch	S72°E 41.34 Feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 01, 1995