

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
(County)

Located In: Corner Code #

| | | |
|------------------------------------|---------------------------|--------------|
| 1. Public Land Survey | T <u>48N</u> R <u>42W</u> | <u>A-3</u> ✓ |
| | T _____ R _____ | _____ |
| | T <u>48N</u> R <u>43W</u> | <u>M-3</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded December 7 1994
at 4:15 o'clock P. M. In
Liber 3 page 236
Jessie M. Arley deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
Section corner common to Sections 6 and 7, T48N, R42W and Sections 1 and 12, T48N, R43W.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, John R. Garske, in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt in 1847. Set post from which a 26" hemlock bears S40°E, 20 links and a 24" hemlock - N20W, 85 links.
1916 map by D.S.S. and A.R.R. Co. shows corner ties.
March 1964 survey by V. Arcand shows corner, however does not call out corner description.
1966 M.D.O.T. map corner shown with ties as follows: Light pole - N41°W, 40.17 feet; 12" maple - S65°E, 52.95 feet; 6" maple - S30°W, 37.18 feet.
Recorded by E. Applekamp RLS 17610 in T48N, R43W, Liber 1, Page 7 - Code M-3.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence can be found due to logging activity, road and utility construction.
Found a 1 1/2" iron pipe (bent) marking the corner position. This corner position has been used for many years by several surveyors. Local residents agree to it being the section corner and is the only possible corner position due to all the development referenced to it.
Act 74 record research on file.

ONTONAGON COUNTY
PEER APPROVED
Earl W. Applekamp
Ont Co Rep
11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I updated the corner position to state and county specifications by setting a 5/8" x 24" rebar with a 3 1/4" aluminum cap 3" below the paved road surface stamped: County Remonumentation; S-1; S-12; S-6; S-7; T48N, R43W, R42W; 1994; RLS 28410. I established the following bearing trees and reference objects: A reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position - Due east - 41.76 feet with a 6" steel rail with sign 0.92 feet away; light pole - N41°W, 40.17 feet; 12" maple - S65°E, 52.95 feet; 6" maple - S30°W, 37.18 feet.

Signed by *John R. Garske* Date 11/28/94
Surveyor's Michigan License No. 28410