

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic & ontonagon Located In: Corner Code #
 (County)

- | | | |
|------------------------------------|-----------------------------------|-----------------|
| 1. Public Land Survey | T <u>48N</u> R <u>42W</u> | <u>B-13</u> |
| | T 47N R 42W | B-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SURVEY & REMONUMENTATION

MAY 22 1997

Register of Deeds, Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

N 1/4 cor. of Sec. 6, T.47 N., R.42 W.
 S 1/4 cor of Sec. 31, T.48 N., R.42 W.

I, John P. Goss in a field survey on March 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|----|----|----|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Wm. A. Burt on August 10, 1848. Set a Hemlock Post. Original Bearing Trees: Hemlock 16"- N 27°W-45 links; Lynn 14"- N 38°E-14 links.

John P. Goss in 1983 using MDOT witnesses set a 1 inch iron rebar and recorded this corner in Liber 2 pages 308 and 309 of Gogebic County Land Corners: 8" Maple- N 60°E-11.28'; 4" Maple- S 40°W- 13.78'; 9" Maple- N 29°W- 33.46'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1 inch iron rebar marking the corner position and it checked with the witnesses in John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with County Register of Deeds Office.

PEER GROUP APPROVED
Carl W. Applekamp 4-06-95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the 1 inch iron rebar I set a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; 1/4; S-6; S-31; T.47-48 N.; R.42 W.; 1995; P.S. 23509. I established the following bearing trees and reference objects.

- | | | |
|---------------------------------|---------|--------|
| D.H. Nail & Tag in 10" Maple | N 60° E | 11.28' |
| D.H. Nail & Tag in 6" Maple | S 40° W | 13.78' |
| D.H. Nail & Tag in 12" Maple | N 24° W | 33.66' |
| D.H. Nail & Tag in 16" Basswood | S 76° E | 18.81' |
| Steel Sign Post | N 80° W | 1.21' |



Signed by John P. Goss Date March 30, 1995
 Surveyor's Michigan License No. P.S. 23509

244