

# SURVEY & REMONUMENTATION

APR 25 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### COMMISSION

For corners in

ONTONAGON  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	48	R	42	C-1 ✓
	T		R		
	T	49N	R	42W	C-13
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Recorded Aug. 31 1994  
at 2:03 o'clock P. M. in  
Liber 3 page 201  
Julie Masley Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Section corner, Sections 5, 6, 31, 32, T48-49N, R42W

I, Earl W. Applekamp, in a field survey on June 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, August 10, 1848.  
Set an Ironwood Post.

Original bearing trees:

Hemlock	26"	N50°E	46 links
Hemlock	8"	N45°W	10 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1978 I found a 1" pipe ( in poor condition) at the corner position and set a 1" drill steel inside it. The pipe location agreed with an original call of 0.25 chains West along the Section line to the "South end of a rock ledge 20 feet high". I remonumented the corner and established accessories to state and county specifications as noted below.

ONTONAGON COUNTY  
PEER APPROVED  
Earl Applekamp  
Aug 17, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" long split base aluminum monument with a 3/4" aluminum cap stamped to read: County Monumentation, S-31, S-32, T49N R42W & S-5, S-6, T48N R42W, 1994, P.S. 17610 I established the following bearing trees and reference objects:

Steel sign post - N35°W,	2.19 feet	6" Maple	S48°W, 9.60 feet
16" Maple	N74°E, 18.85 feet	7" Maple	S05°E 28.00 feet

Signed by Earl W. Applekamp Date August 10, 1994  
Surveyor's Michigan License No. 17610