

**SURVEY & REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48 R 42	C-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded December 5 1994  
at 2:05 o'clock P. M. in  
Liber 3 page 221  
J. J. M. Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 7, 8, 18, 17, T48N R42W

I, Earl W. Applekamp in a field survey on October 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, Deputy Surveyor, August 1848.  
Set Tamarack Post.

Original Bearing Trees:

Spruce 12" N28°E 35 Links (23.10')  
Spruce 10" N31°W 32 Links (21.12')

**ONTONAGON COUNTY**

**PEER APPROVED**  
EW Applekamp  
Ont Co Rep  
12-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a 2" pipe. This pipe was used for surveys in Section 7, by V. Arcand in 1960. On March 27, 1974 the corner was recorded in Liber No. 1 L.C., page 9. I accepted the position of the corner and remonumented to corner as shown below.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/4"x30" aluminum pipe stamped to read: County Remonumentation S7, S8, S18, S17, T48N R42W, 1994, P.S. 17610. I established the following bearing trees and reference objects.

Black Ash 9" S52°W 38.13'  
Black Ash 12" N59°E 19.16'  
Black Ash 7" S57°E 18.50'  
Steel Sign Post North 1.95'



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date November 28, 1994