

# SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM  
Ontonagon County  
LC 3/331 JEM Fee: 9.00  
Page 1 of 1

For corners in

Ontonagon <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>48N</u> R <u>42W</u>	<u>C-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

One-quarter corner common to Sections 18 and 17, T48N, R42W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on September 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- On August 10, 1848, Austin Burt set an ironwood post from which a 12" sugar bears N20°W, 27 links and a 16" sugar - N74°E - 8 links.
- Survey dated May 13, 1978, by Earl Applekamp, RLS 17610, found a 2" diameter iron pipe at 1/4 corner location which is shown on his Plat of Survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 2" iron pipe as noted above and accepted corner as being in correct position as it has been used in several surveys of record.

Record research on file with Register of Deeds.


**PEER GROUP APPROVED**

*Earl Applekamp 9-20-95*  
**COUNTY REPRESENTATIVE**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N; R42W; 1/4; S-18; S-17; 1995; RLS 28410, from which the following bearing trees and/or reference objects:

- 9" sugar - N53°E - 19.38 feet
- 11" sugar - S53°E - 20.00 feet
- 10" sugar - N42°W - 22.84 feet
- 6 foot steel rai with sign - S76°W - 1.41 feet



Signed by John R. Garske Date 9-19-95  
Surveyor's Michigan License No. 28410