

SURVEY & REMONUMENTATION

APR 26 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
(County)

Located In: Corner Code #/

1. Public Land Survey

48
T R 42
T 49N R 42W

D-1 ✓
D-13

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

¼ Corner 5 & 32, T48, 49N R42W

I, Earl W. Applekamp, in a field survey on October 31, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William A. Burt, Deputy Surveyor, August 1884.
Set Cedar Post. Original bearing trees:

Hemlock 28" N55°E 17 Links - Cedar 9" N44°W 13 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A one inch drill steel was set at Corner in July 1978 by Earl W. Applekamp.
Corner was set by single proportionate measurements at that time.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½" x 30" long aluminum pipe with a 3¼" Cap stamped to read: County Remonumentation, ¼, S5, S32, T48N R42W; T49N R42W, 1994, P.S. 17610. I established the following bearing trees and reference objects.

9" Maple N09°W 22.53' - 7" Maple S57°W 16.74'
9" Maple S24°E 18.73' - Steel sign post North 1.85'

Recorded December 5 1994
at 2:05 o'clock P. M. In
Liber 3 Page 223
Julie Marley Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4	3	2	1						
3													
4	7		8	9	10	11	12						
5													
6	18		17	16	15	14	13						
7													
8	19		20	21	22	23	24						
9													
10	30		29	28	27	26	25						
11													
12	31		32	33	34	35	36						
13													

ONTONAGON COUNTY

PEER APPROVED

EW Applekamp
Ont Co Rep
11-30-94



Signed by Earl W. Applekamp

Date November 21, 1994

Surveyor's Michigan License No. 17610