

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 4/ 76 JEM Fee: 9.00
 06/10/96
 15:44
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 42W	D-5
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner common to Sections 8 & 17, T48N R42W.

I, Earl W. Applekamp, in a field survey on May 28, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 08, 1848. Set Cedar Post.

ORIGINAL BEARING TREES:

Cedar 10" S61°W 28 links
 Cedar 9" N38°E 40 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was established by single proportionate measurement between opposite Section Corners to the East & West. At this location there were two trees blazed about 30-40 years ago.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 6-06-96

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x48" aluminum rod with a 3 1/4" cap stamped to read: County Remonumentation, 1/4, T48N R42W, S8, S17, 1996, P.S. 17610. I established three bearing trees and one other reference object.

9" Cedar N45°W 10.07 feet - 13" Cedar S77°E 24.41 feet
 8" Cedar N07°E 35.51 feet - Steel Sign Post West 1.55 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date May 3, 1996