

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code ##

1. Public Land Survey Section 20T 48N R 42W D-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Recorded August 31 1994
 at 2:05 o'clock P. M. in
 Liber 3 page 206
Julie Marley, Deputy
 Registrar of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John R. Garske, in a field survey on May 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, U.S.D.S., on August 2-12, 1848. Set hemlock post. Original Bearing Trees: 16" hemlock - S20°W - 5 links; 10" hemlock - N55°E - 21 links

Keweenaw Land Assoc. Ltd. date unknown - Found tag at corner location.

Survey by Earl Applekamp, RLS 17610, in 1985-89, indicated on iron pipe marking the 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" iron pipe marking the corner position and accepted corner location as being true due to its longevity and use in many surveys of record. I remonumented the corner and updated accessories as noted below to state and county specifications.

Research on file with County Remonumentation Program Representative.

ONTONAGON COUNTY
PEER APPROVED
Earl Applekamp Co. Rep
 8-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" iron pipe with a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Monumentation, 1/4, S-17, S-20, T48N, R42W, 1994, RLS 28410. I established the following bearing trees and reference objects:

- Steel sign post - N60°E - 1.70 feet
- 8" spruce - N15°E - 21.00 feet
- 8" cedar - S73°W - 15.16 feet
- 4" S. maple - S01°W - 22.42 feet

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 6/8/94

