

DEC 1 6 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/ 73 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 42W	E-4
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner common to Sections 8 & 9, T48N R42W.

I, Earl W. Applekamp, in a field survey on June 04, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 08, 1848. Set Maple Post.

ORIGINAL BEARING TREES:

Cedar 12" S60°E 44 links
Cedar 16" N75°W 25 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A yellow tag and some blazes were found near the corner position. The corner was re-established by single proportionate measurement on line between the SE Corner of Section 8 and the N 1/16 Corner. This is explained in detail in the research file.

Research on file with the Ontonagon County Remonumentation Representative.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
6-06-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" aluminum pipe with a 3/4" cap stamped to read: County Remonumentation, 1/4, T48N R42W, 1966, P.S. 17610. I established 3 bearing trees and one other reference object.

15" Cedar N46°W 29.62' 10" Cedar 40°E 32.25'
12" Cedar S45°W 36.40' Steel Sign Post East 1.15'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date JUNE 06, 1996