

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon (County)

Located In: Corner Code --#

- 1. Public Land Survey Section 20T 48N R 42W E-7
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Recorded August 31 1994 at 2:05 o'clock P. M. in Liber: 3 page 205 Julie Marley Deputy Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Section corner to Sections 16, 17, 20 and 21.

I, John R. Garske, in a field survey on May 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 7.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S., on August 2-12, 1848. Set maple post. Original Bearing Trees: 21" Y. birch - S35°E - 22 links; 18" hemlock - N15°W - 28 links
Keweenaw Land Assoc. Ltd. - Date: unknown. Found U.S.F.S. location poster on the east side of 16" hemlock.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 2" square wood post (cedar) at the corner position and Keweenaw Land Assoc. Ltd. location poster on 16" hemlock bearing N73°W - 12.5 feet with an old rusted Forest Service Poster. I found the decayed remains of the yellow birch bearing tree at the record distance from the post. I also found a large stump hole with decayed hemlock bark in root holes at the other original bearing tree location. I accepted the post as marking the original corner position based on its location, use and the two bearing tree remains found.

Research on file with County Remonumentation Program Representative.

ONTONAGON COUNTY

PEER APPROVED

Earl Applekamp Co. Rep. 8-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum county monumentation cap stamped to identify the corner from which I established the following accessories:

- 12" hemlock - N20°W - 18.74 feet
12" hemlock - S67°W - 31.82 feet
3" R. maple - S37°E - 5.30 feet
8" hemlock - N65°E - 22.74 feet
Steel sign post - Due North - 1.07 feet

Signed by John R Garske Date 8/8/94
Surveyor's Michigan License No. 28410

