

**SURVEY &
REMONUMENTATION**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Ontonagon
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>48N</u> | R | <u>42W</u> | <u>E-10</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Recorded December 7 1994
at 4:15 o'clock P. M. in
Liber 3 page 239
Jessie Marley Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
One-quarter corner common to Sections 28 and 29, T48N, R42W

November 3 1994

I, John R. Garske, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt - August 1848. Set Ironwood post from which a 10" sugar bears - N26°W, 18 links and a 20" hemlock bears - S31°E, 22 links.

**ONTONAGON COUNTY
PEER APPROVED**

Earl W. Applekamp
Co. Rep. 11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence of the corner position could be found due to logging activity. Reestablished the corner position by the single proportionatal method measurement between the found meander corner to the south and the section corner north in accordance with the original notes.

Corner record research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set corner position to state and county specifications by setting a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: 1/4; S-29; S-28; T48N, R42W; 1994; RLS 28410. Established the following bearing trees and reference object: 6" maple - N09°E, 17.85 feet; 6" ash - Due West - 10.35 feet; 7" ash - S31°E, 22.86 feet; 6 foot steel rail with sign - Due East, 1.74 feet.

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/20/94

