

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ONTONAGON
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 48 R 42
 T 49N R 42W

F-1 ✓
F-13

2. Property Controlling in Section

S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner 4 - 33 T48, T49N R42W

Recorded December 19 1994
 at 2:30 o'clock P. M. in
 Liber Survey 3 page 249
Julie Marley
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Earl W. Applekamp, in a field survey on December 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor, August 1848. Set Sugar Post.

Black Ash 6" N81°E 37Links (24.42 Feet)
 Yellow Birch 12" N17°W 33Links (21.78 Feet)

ONTONAGON COUNTY
PEER APPROVED
Earl W. Applekamp
Ont Co Rep
 12-15-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position is a 1/2" I.P. in a box near the centerline of Highway M-28. This monument has been at this location for 30 plus years. I have personally used it for several surveys. I accepted the corner as being in the proper position and monumented as described below.

monument
 Reference named below is a 2 1/4"x30" aluminum pipe with a 3/4" cap stamped to read: COUNTY REMONUMENTATION R.M., 1/4 S.4, S.33, T48, T49N, R42W, 1994, P.S. 17610.

Research on file with the County Remonumentation Program Representative.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I capped the existing 1/2" Iron Pin (in a box in Hwy M-28) with a 3 1/4" brass cap stamped to read: COUNTY REMONUMENTATION, 1/4, S.4, S.33, T48, T49N, R42W, 1994, P.S. 17610. I established the following witness objects:

- 1/2" Iron Pin in blacktop road in line with corner & reference monument N07°E 34.60 feet
- Power Pole N86°E 139.63 feet
- Power Pole S31°E 46.80 feet
- Reference Monument described in "B", S07°E 53.10 feet

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date December 12, 1994

249