

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon

(County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>48N</u> R <u>42W</u> | <u>F-11</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

Recorded December 7 1994  
 At 4:15 o'clock P. M. In  
 Liber 3 page 237  
*Jessie M. Bailey Deputy*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 One-quarter corner common to Sections 28 and 33, T48N, R42W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on October 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt - August 1848. Set a maple post from which a 10" hemlock bears S25°E, 14 links and a 10" hemlock - N38°W, 28 links.

On July 25, 1991, I found a capped rebar set by Robert Mick, RLS 16936, date unknown, along with a squared wood post and a 12" blazed cedar tagged with the following names and dates: A.E. Pierce - 6/4/36' H.W. Cole, L.A. Pointe - 8/27/41; Turney - 3/26/52. Cedar bears S35°E, 6.0 feet, 3 tags in a 12" cedar with blaze, bears - N10°W, 11.36 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found due to logging activity. I accepted the found rebar as noted above which has been used in various surveys and accepted by timber companies as the one-quarter corner due to its longevity and the development referenced to it.

Corner record research on file.

**ONTONAGON COUNTY  
PEER APPROVED**

*Earl W. Applekamp*  
 Co. Rep.  
 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I updated the corner position to state and county specifications by replacing rebar with a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; 1/4; S-28; S-33; T48N, R42W; 1994; RLS 28410. I established the following bearing trees and reference object: 12" cedar - N10°W, 11.36 feet; 18" hemlock - N52°E, 18.94 feet; 6" maple - S87°E, 8.74 feet; 6 foot steel rail with sign - S55°W, 1.30 feet.



Signed by *John R. Garske*

Date 11/25/94

Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

FED No. V-11 237