

**SURVEY & REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48 R 42	G-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded December 5 1994  
at 2:05 o'clock P. M. in  
Liber 3 page 222  
*Juan M. Miley* Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

Sections 3, 4, 9, & 10, T48N R42W

I, Earl W. Applekamp in a field survey on November 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, August 1848.  
Set Cedar Post.

Original Bearing trees:

Elm 14" S55°E 91 Links (60.06')  
Elm 10" N77°W 30 Links (19.80')

**ONTONAGON COUNTY**  
**PEER APPROVED**  
*Earl W. Applekamp*  
Ont Co Rep  
11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a survey in 1993 I found a 1/2" threaded iron rod set at the corner location. The location of this iron rod was in agreement with the calls to a creek to the West and South. The iron rod was tied to trees and cutting lines were evident. I accepted the location and set a more substantial 1" Drill Steel and tied to trees. In 1994 I remonumented the corner as shown below.

Research on file with the County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner location, I set a 2 1/4"x30" aluminum pipe with a 3 1/4" cap over a 1" Drill Steel. Cap stamped to read: County Remonumentation, S3, S4, S9 S10, T48N R42W, 1994, P.S. 17610. I established the following bearing trees and reference objects.

Black Ash 20" N75°W 24.70' - Black Ash 12" N01°E 25.55'  
Black Ash 16" N55°E 19.00' - Steel Sign Post 0.80'



Signed by Earl W. Applekamp Date November 28, 1994  
Surveyor's Michigan License No. 17610