

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
 (County)

Located In: _____ Corner Code # _____
 1. Public Land Survey T 48N R 42W _____ G-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Recorded December 7 1994
 at 4:15 o'clock P. M. In
 Liber 3 page 235
Janis M. A. Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section corner common to Sections 27, 28, 33 and 34, T48N, R42W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt, August 1848. Set a hemlock post from which a 16" hemlock bears - S75°E, 14 links and a 16" hemlock - N67°W, 13 links.

ONTONAGON COUNTY
PEER APPROVED

Earl W. Applekamp
 Co Rep 11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a post with a champion tag along with a 18" blazed cedar with a USFS tag and a 16" blazed hemlock with a Keweenaw tag.

I was able to find adequate original evidence combined with existing corner information found in the field by Keweenaw Land personnel to place the corner in its original position. I found a stump hole and mound to identify the original bearing tree to the northwest, along with the swamp call 3 chs west. These measurements in conjunction with the blazed 18" cedar with a USFS tag matched so the corner position was established and accepted.


Corner record research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I monumented the corner position to state and county specifications by setting a standard Bernsten aluminum monument with a stamped 3 1/4" aluminum cap. I established the following bearing trees and reference object: 3" maple - N47°E, 18.60 feet; 6" cedar - S23°E, 4.70 feet; 8" balsam fir - N57°W, 17.31 feet; 6 foot steel rail with sign - due south, 1.96 feet.

Signed by *John R. Garske*
 Surveyor's Michigan License No. 28410

Date 11/28/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983