

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>48N</u> R <u>42W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded December 7 1994
 at 4:15 o'clock P. M. in
 Liber 3 page 234
Julia Marley
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 One-quarter corner common to Sections 33 and 34, T48N, R42W.

I, John R. Garske, in a field survey on October 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt, August 1848. Set a hemlock post from which a 8" cedar bears S54°E, 28 links and a 10" hemlock - N37°W, 30 links.

Tag in original 8" cedar bearing tree with the following names and dates: Joe & Wm. J. Weston - 7/23/40; H.W. Cole & L.LaPoint - 9/29/41; C.R. Ottari - 1/26/42; Smith - 10/9/42.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I was able to reestablish the corner position by evidence found. The original bearing trees, one being a fallen 16" cedar tagged as noted above with a 4" deep blaze and a hemlock mound matching the other original bearing and distance.

Corner record research on file.

ONTONAGON COUNTY
PEER APPROVED

Earl W. Applebaum
 Ont Co Rep
 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I monumented the corner position to state and county specifications by setting a standard Bernsten aluminum monument with a stamped 3 1/4" aluminum cap stamped to indicate the corner position. I established the following bearing trees and reference object: 10" hemlock - S78°E, 16.68 feet; 8" ash - S08°W, 9.02 feet; 12" sugar - N20°W, 19.11 feet; 6 foot steel rail with sign - due west, 1.97 feet.

Signed by John R Garske
 Surveyor's Michigan License No. 28410

Date 11/28/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983