

# SURVEY & REMONUMENTATION

APR 25 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION  
ONTONAGON  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>48</u>	R <u>42</u>	(H-1) ✓
	T _____	R _____	
	T <u>49N</u>	R <u>42W</u>	H-13
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____	
	S _____	T _____	
3. Miscellaneous Property in Sec.	S _____	T _____	
	S _____	T _____	

Recorded December 19 1994  
at 2:30 o'clock P. M. in  
Liber Survey 3 page 248  
Judith A. Auley Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 Corner, S.3 & 34, T48, T49N R42W

I, Earl W. Applekamp, in a field survey on December 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor, August 1848. Set Sugar Maple Post.

Original Bearing Trees:

Sugar	12"	N19°W	15 Links	( 9.90 feet)
Lynn	14"	N38°E	45 Links	(29.70 feet)

**ONTONAGON COUNTY  
PEER APPROVED**

*Earl W. Applekamp*  
*Dist. Co. Rep*  
*12-15-94*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found. Highway M-28 has obliterated all original evidence. Corner was reset by single proportionate measurement on line between the NW & NE Corner of Section 3.

Research on file with the County Remonumentation Program Representative.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a PK NAIL in the blacktop surface of Highway M-28. I set two reference monuments, one North and one South which are 2 1/4"x30" aluminum pipes with a 3 1/4" cap stamped to read: County Remonumentation R.M., 1/4, S.3, S.34, T48 T49N, R42W, 1994, P.S. 17610. These two monuments and 1/4 corner are on line. The following reference monuments and objects were used to tie in the corner.

Reference Monument North	52.12 Feet	- 3' Black Ash	S07°E	62.34 Feet
Reference Monument South	52.09 Feet	- 8" Maple	N23°W	75.43 Feet

Signed by Earl W. Applekamp Date December 13, 1994  
Surveyor's Michigan License No. 17610

248