

**SURVEY & REMONUMENTATION**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
G.D.  
G.D.  
G.D.

COMMISSION

For corners in

ONTONAGON  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 48 R 42  
T \_\_\_\_\_ R \_\_\_\_\_  
T 49N R 42W  
T \_\_\_\_\_ R \_\_\_\_\_

I-1 ✓

I-13

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Recorded October 19 1994  
at 2:13 o'clock P. M. in  
Liber 3 page 211  
Julie Marley deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Section Corner 2, 3, 34 & 35, T48 & 49N R42W

Earl W. Applekamp October 01 19 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Yellow Birch Post  
Sugar 12" N69°E 32 links (21.12 feet)  
Hemlock 10" N18°W 38 links (25.08 feet)

**ONTONAGON COUNTY**  
**PEER APPROVED**

*Earl W. Applekamp*  
Ontonagon Co. Rep.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe with 3 ties at the corner location and accepted this being the corner location because of the long time this corner was marked. In a survey conducted in 1993 this location was checked with established corners to the South and West and was in general agreement with the original survey. Based on all this evidence I replaced the 1 1/2" pipe with a permanent monument described below.

Research on file with County Remonumentation Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" long aluminum pipe with a 3 1/4" cap, stamped to read: County Remonumentation, Section 2, 3, 34, 35, T48N & T49N, R42W 1994, P.S. 17610. The corner was tied to the following trees and objects.

Twin Oaks	14"	N06°E	35.59'	Sugar	14"	S73°E	15.35'
White Ash	12"	S42°W	22.65'	Steel Sign Post	North	1.75'	

Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date October 07, 1994

