

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R41W	A-6
	T48N R42W	M-6 ✓
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REMONUMENTATION
 OCT 30 1997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 13 & 18, T48N R41W & 42W.

I, Earl W. Applekamp, in a field survey on Aug. 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6	●	18		17		16		15		14		13	●
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, August 12, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

- 9" Spruce S22°E 10.56 feet
- 9" Spruce N62°W 21.12 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 9-17-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Apparent corner position is in the centerline of a North-South gravel county road.* Corner was re-established by single proportionate measure between opposite section corners North & South and in the centerline of the gravel road.

*I found a 1" bent pipe 1.2 feet below T/gravel 1 1/2' West of the centerline of the road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a stamped 3" cap, 6" below top of gravel road surface. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, R42W, R.M., 1/4, S13, S18, 1997, P.S. 17610. I also established 3 other bearing trees or objects.

- 9" Aspen S75°-34'-38"W 56.55' - Power Pole N49°-48'-48"W 50.86'
- REF. MON. N88°-52'-46"E 33.01' - 4 1/2" Spruce N50°-48'-05"E 48.03'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 16, 1997