

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 41W	A-8
	T48NR 42W	M-8 ✓
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

REMO

OCT 3 1997

COMMISSIONER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Section 19, T48N R41W & Section 24, T48N R42W.

I, Earl W. Applekamp, in a field survey on Sept. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, August 12, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

18" Cedar N38°E 11.88 feet  
 16" Cedar N40°W 3.96 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. Apparent corner falls in a well used gravel lane and a dirt lane running 1/2 mile East. There are fields East, North and South of the corner. I re-established the corner by single proportionate measure and on line between opposite section corners North & South. This position is near the centerline of the lane North & South and in the centerline of the lane running East.

Research on file with the Ontonagon County Remonumentation Program Representative.

FREE GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REPRESENTATIVE  
 9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" split aluminum pipe with a 3" cap 5" below top of gravel, stamped to read: County Remonumentation, T48N R41W, R42W, 1/4, S19, S24, 1997, P.S. 17610. I established three bearing trees and a reference object.

6" Aspen S46°W 23.93' - 9" Aspen N18°W 54.03'  
 6 1/2" W. Birch N84°W 35.86' - Steel Sign Post, West 18.57'



Signed by *Earl W. Applekamp*  
 Surveyor's Michigan License No. 17610

Date September 16, 1997