

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>48N</u> R <u>43W</u>	<u>A-5</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>44W</u>	<u>M-5 (Gogebic)</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sec. Cor. 7, 18, 12 & 13; T.48 N., R.43-44 W.

I, Richard L. Drahn in a field survey on October 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Aug. 13, 1847. Original B.T.s --- Sugar 18" S.76 W. 16 links (10.56') --- Sugar 16" N.71 E. 47 links (31.02')
 Corner restored by Richard L. Drahn, RLS 21564 on 2/5/79 from the stump holes of the two GLO B.T.s, line trees south and east and distances to recovered corners south, east and west. He set a 2" iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 5" (8") Sugar Maple N.03E. (N.03 E.) 25.05' (24.92') --- 6" (8") Sugar Maple S.54 E. (S.53 E.) 27.35' (27.04') --- 6" (9") Sugar Maple S.54 W. (S.51 W.) 25.15' (25.28') --- 7' Metal sign post N.24 W. (N.25 W.) 2.45' (2.30') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. A shallow depression from the SW B.T. is all that remains of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Bearing tree referenced:

6" Sugar Maple S.82 W. 14.52'

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 10-16-96



Signed by Richard L. Drahn Date October 9, 1996

Surveyor's Michigan License No. 21564