

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code #:

- | | | |
|------------------------------------|---------------------------|----------------------|
| 1. Public Land Survey | T <u>48N</u> R <u>43W</u> | <u>A-6</u> ✓ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T <u>48N</u> R <u>44W</u> | <u>M-6 (Gogebic)</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SURVEY & REMONUMENTATION
MAY 22 1997
COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner 18 & 13: T.48 N., R.43-44 W.

I, Richard L. Drahn in a field survey on October 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Gogebic County

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt On August 13, 1847. Original B.T.s --- Hemlock 18" S.56 W. 29 links (19.14') --- Hemlock 14" N.66 E. 36 links (23.76') Corner restored by Richard L. Drahn, RLS 21564 on 2/6/79 from the remains of the two original B.T.s and from a line tree north and from distances to recovered corners ½ mile north and south. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 9" Sugar Maple (10" cut stump) N.36 E. (N.25 E.) 24.39' (24.37') --- 8" (10") Sugar Maple N.81 E. (N.81 E.) 32.72' (32.83') --- 7" (12") Sugar Maple S.82 W. (S.83 W.) 19.31' (19.22') --- 7' Metal sign post N.35 E. (N.20 E.) 1.35' (1.35')---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in Liber 1, Page 183 on 4/11/80.
 Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. Stump holes are all that remain of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing tree referenced:

6" Sugar Maple N.17 E. 16.07'

PEER GROUP APPROVED
Carl W. Applikans
 COUNTY REPRESENTATIVE 10-16-96



Signed by Richard L. Drahn

Date October 10, 1996

Surveyor's Michigan License No. 21564