

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>48N</u> R <u>43W</u>	<u>A-7</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>44W</u>	<u>M-7 (Gogebic)</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

Sec. Cor. 18, 19, 13 & 24: T.48 N., R.43-44 W.

I, Richard L. Drahn in a field survey on October 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Aug. 13, 1847. Original B.T.s --- Tamarack 10" S.71 W. 21 links (13.86') --- Tamarack 12" N.53 E. 49 links (32.34')---

Corner restored by Donald D. Lappala, RLS 12585 from the point of the original Spruce post, the remains of the two original B.T.s (one still scribed) and from an original, scribed W.T. stub. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s.: 5" (7") Cedar (now dead) N.57 E. (N.58 E.) 24.7' (24.64') --- 8" (10") Cedar S.53 E. (S.52 E.) 8.5' (8.37') --- 4" Cedar (5" dead Cedar stub) S.75 W. (S.76 W.) 13.3' (13.28') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in USFS Liber, Page N-25 on 3/31/69.

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. Identifiable remains of the two original B.T.s (one still scribed) and the decayed remains of the GLO W.T. still remain from the original survey.

PEER GROUP APPROVED

Earl W. Lappala

COUNTY REPRESENTATIVE 10-16-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

4" X 4" Cedar sign post	S.56 W.	1.25'
6" Steel sign rail	East	2.25'
9" Cedar	N.39 W.	16.52'
11" Cedar	S.51 W.	26.32'



Signed by Richard L. Drahn

Date October 10, 1996

Surveyor's Michigan License No. 21564