

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/122 JEM Fee: 9.00
07/11/96 09:08
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 43W	C-1
	T ___ R ___	
	T ___ R ___	
	T 49N R 43W	C-13
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Sec. Cor. 5, 6, 31 & 32; T.48-49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on Aug. 16, 1847. Original B.T.s --- Hemlock 16" N. 20 E. 30 links (19.80') --- Y. Birch 12" N.19 W. 35 links (23.10') --- F. Brotherton, on 4/19/35 recovered the Y. Birch still scribed. Donald D. Lappala, RLS 12585 on 6/24/70 restored the corner from the remains of the two original B.T.s and Brothertons tag/B.T. He set a 2 1/2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 13" (13") Sugar Maple N.41 W.(N.41 W.) 29.7' (29.77') --- 7" (10") Black Ash N.72 E. (N.75E.) 30.6' (30.55') --- 7" (11") White Ash S.65 W. (S.66 W.) 21.5' (21.46') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in USFS Liber, Page A-5 on 9/14/72. Act 74 research form on file with Ontonagon County records. Recovered the monument as described and the bearing trees as noted in parentheses above. A stump hole from the Hemlock is all that remains of the original bearing trees.

PEER GROUP APPROVED
Earl W. Repole
COUNTY REPRESENTATIVE
07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:
6' Steel sign rail S.25E. 2.4'



Signed by Richard L. Drahn Date June 13, 1996

Surveyor's Michigan License No. 21564

USFS A-5 (T.40 N.)
Z-5 (T.49 N.)