

DEC 16 1996

**COMMISSION**

JUDITH D. ROEHM  
 Ontonagon County  
 LC 4/118, JEM Fee: 9.00  
 07/11/96  
 09:06  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>43W</u>	<u>F-1</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>49N</u> R <u>43W</u>	<u>F-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

¼ Corner 4 & 33; T.48-49N., R.43 W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2						●							
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Richard L. Drahn in a field survey on June 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by John Burt on Aug. 16, 1847. Original B.T.S --- Y. Birch 12" N.27 E. 24 links (15.84') --- 6" Y. Birch N.52 W. 10 links (6.6') --- Corner restored by Donald D. Lappala, RLS 12585 on 9/3/68 from stump of the first B.T. and from the live, still scribed 12" original bearing tree. He set a 2" dia. iron pipe monument with a 3" stamped brass cap and the following new B.T.s: --- 9" Cedar (10") N.50 E. (N.51 E.) 21.5' (21.60') --- 6' (7") Cedar (now a dead stub) S.32 W. (S.32 W.) 14.5" (14.60') --- 3' X 2½' X 2' Red sandstone boulder with a chiseled "X" on top N.46 W. (N.43 W.) 14.3' (14.3'). ---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Ontonagon County in USFS Liber, Page A-11 on 4/1/69.  
 Act 74 research form on file with Ontonagon County records.  
 Recovered the monument as described and the bearing trees as noted in Parentheses above.

The original B.T. at N.27 E. is now a Yellow Birch stump, decayed to below ground line. The B.T. at N.52 W. is now a 12" Yellow Birch stub with GLO blazes and the measuring notch still visible.

PEER GROUP APPROVED  
*Carl W. Applekamp*  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:** 07-08-96

**Bearing objects referenced:**

4" X 4" Cedar sign post	S.82 W.	3.35'
6' Steel sign post.	S.53 E.	3.1'
7" Hemlock	S.72 E.	24.85'



Signed by Richard L. Drahn Date June 13, 1996

Surveyor's Michigan License No. 21564

USFS A-11 (T.48 N.)  
 Z-11 (T.49 N.)