

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/124 JEM Fee: 9.00
07/11/96 09:08
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>43W</u>	<u>G13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>48N</u> R <u>43W</u>	<u>G-1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 3, 4, 33 & 34; T.48-49 N., R.43 W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	8	7	6	5	4	3	2	1					
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

Richard L. Drahn in a field survey on June 17, 1996,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by John Burt on Aug. 16, 1847. Original B.T.s: ---
Maple 18" N.82 E. 47 links (31.02') --- Y. Birch 24" N.05 W.39 links
(25.74'). Corner restored by Donald D. Lappala, RLS 12585 on 9/3/68
from the scribed remains of the Y. Birch bearing tree. He set a 2"
dia. iron pipe with a 3" stamped brass cap and the following new B.T.s:
--- 11" (14") Yellow Birch N.81 W. (N.81 W.) 20.6' (20.66') --- 5" (10")
Sugar Maple N.84 E. (N.86 E.) 64.3' (64.32') --- 6" (10") Yellow Birch
S.27 E. (S.25 E.) 45.2' (45.27') --- Corner recorded in Ontonagon
County in USFS Liber, Page A-13 (T.48 N.) on 4/1/69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in
parentheses above.

A large, badly decayed Yellow Birch stump is all that remains of the
original bearing trees.

PEER GROUP APPROVED
Earl W. Grolakamp
COUNTY REPRESENTATIVE
07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

4" X 4" Cedar sign post S.37 E. 2.35'
6' Steel sign rail S.60 W. 3.6'



Signed by Richard L. Drahn

Date June 20, 1996

Surveyor's Michigan License No. 21564

USFS Z-13 (T.49 N)
A-13 (T.48 N)