

DEC 1 6 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 LC 4/127 JEM Fee: 9.00
 Page 1 of 1

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N. R 43W.	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T 48N. R 43W.	H-1 ✓
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner 34 & 3; T.48-49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 17, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	28	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on Aug. 16, 1847. Original B.T.s: --- Hemlock 24" N.35 E. 22 links (14.52') --- Maple 10" N.12 W. 5 links (3.30') --- H. J. Trevanon recovered the Hemlock still scribed on 8/12/35. Corner restored by Richard L. Drahn, RLS 21564 on 10/22/81 from the remains of the two original B.T.s and a line tree east. He set a 2" dia. aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 9" (12") Red Maple N.10 W. (N.12 W.) 27.13' (27.12') --- 18" (20") Hemlock N.87 E. (N.86 E.) 34.32' (34.25') --- 15" (16") Hemlock S.02 E. (S.03 E.) 18.75' (18.76') --- 6' Metal sign post N.69 E. (N.68 E.) 2.25.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in Liber 2, Page 55 on 6/15/82.
 Act 74 research form on file with Ontonagon County records.
 Recovered the monument as described and the bearing trees as noted in parentheses above.

A decayed Hemlock stump and a stump hole still remain from the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

12" Hemlock S.61 W. 30.79'

PEER GROUP APPROVED
Paul W. Applekamp
 COUNTY REPRESENTATIVE
 07-08-96



Signed by Richard L. Drahn Date June 20, 1996

Surveyor's Michigan License No. 21564