

DEC 1 6 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 4/114 JEM Fee: 9.00
Page 1 of 1

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 43W	I-1 ✓
	T R	
	T R	
	T 49N R 43W	I-13
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sec. Cor. 2, 3, 34 & 35; T.48-49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on Aug. 16, 1847. Original B.T.s --- Y. Birch 20" N.37 E. 40 links (26.40') --- Sugar 20" N.35 W. 30 links (19.80') --- F. Brotherton in 1935 recovered the Y. Birch as a 32" scribed yellow birch and recovered a 24" scribed witness tree. Corner restored by Donald D. Lappala, RLS 12585 on 8/16/68 from the remains of the two original B.T.s and the stump of the Sugar Maple witness tree. He set a 2" dia iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 8" (11") Sugar Maple S.84 E. (S.86 E.) 31.4' (31.37') --- 7" (9") Sugar Maple S.05 E. (S.04 E.) 30.7' (30.72') --- 9" (15") Sugar Maple S.86 W. (S.87 W.) 33.4' (33.29') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in USFS Liber, Page A-17 on 9/14/72. Recovered the monument as described and the bearing objects as noted in parentheses above.

The original Y. Birch B.T. is now a badly decayed Yellow birch stump. The original Sugar B.T. is now a stump hole. The Original witness tree recovered in 1935 is now a badly decayed Sugar Maple stump. I nailed Brothertons 1935 location poster to the Cedar sign post.

PEER GROUP APPROVED
Paul W. Appenkamp
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 07-08-96

Bearing objects referenced:

- 4" X 4" Cedar sign post N.35 E. 3.05'
- 6' Steel sign rail N.55 W. 5.3'



Signed by Richard L. Drahn Date June 8, 1996

Surveyor's Michigan License No. 21564

USFS A-17 (T.48 N.)
Z-17 (T.49 N.)