

DEC 16 1996

JUDITH D. ROEHN
Ontonagon County
LC 4/109 JEM Fee: 9.00
07/11/96 08:53
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ontonagon
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 48N R 43W. I-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 2 & 3; T.48 N., R.43 W.

I, Richard L. Drahn in a field survey on June 5, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Aug. 18, 1848. Original B.T.s--- Cedar 12" S.50 W. 15 links (9.90') --- Cedar 14" N.57 E. 10 links (6.60')--- Corner restored by Donald D. Lappala, RLS 12585 on 8/16/68 from the remains of the two original B.T.s, one with scribing. He set a 2" dia iron pipe with a 3" stamped brass cap and the following new bearing trees:--- 7" (11") Hemlock N.58 W. (N.55 W.) 26.5' (26.43') --- 4" (9") Sugar Maple N.09 E. (N.09 E.) 8.5' (8.64') --- 8" Hemlock (13") S.03 W. (S.04 W.) 32.5' (32.38') Corner recorded in Ontonagon County in USFS Liber, Page C-17 on 4/1/69. Act 74 research form on file with Gogebic County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing objects as noted in parentheses above.

The original Cedar at S.50 W. is now a decayed windfall with portions of the GLO blazes still evident. The Cedar at N.57 W. is now a decayed Cedar windfall.

PEER GROUP APPROVED

Carl W. Applekamp
COUNTY REPRESENTATIVE

07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 4" X 4" Cedar sign post S.77 W 1.85'
- 6' Steel sign rail S.72 E. 2.6'



Signed by Richard L. Drahn

Date June 8, 1996

Surveyor's Michigan License No. 21564