

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHM
Ontonagon County
LC 3/371 MEL Fee: 9.00
Page 1 of 1

For corners in	Located In:	Corner Code #
<u>ONTONAGON</u> (County)		
1. Public Land Survey	T <u>48</u> R <u>43</u>	<u>I-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 10 & 11, T48N R43W

I, Earl W. Applekamp, in a field survey on July 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Austen Burt, U.S. Deputy Surveyor on August 16, 1848. Set Black Ash Post.

ORIGINAL BEARING TREES:

Cedar 10" S70°W 33 links (21.78 feet)
Fir 7" N52.5°E 28 links (18.48 feet)

Corner subsequently re-monumented by Kimberly Clark Corporation by single proportionate measurement between NW and SW Corners of Section 11 on July 28, 1976. This corner was recorded on Aug. 9, 1976 in Liber 1,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: LC, page 48

At the corner location I found a 1" galvanized pipe with a 4" cap stamped Kimberly Clark Corporation, T48N R43W, 10, 11, 7-28-76, RLS 14765. The monument projects 6" above ground. I found an Aspen and a Black Ash tree, which were called for as ties to the corner. The corner monument agreed with the bearing and distance given to the two bearing trees. I accepted this as the proper location for the corner and updated the accessories as shown in "C" below.

Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp
COUNTY REPRESENTATIVE

10-18-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position is a 1" galvanized pipe with a 4" cap stamped to read: Kimberly Clark Corp., T48N R43W, 10, 11, 7-28-76, RLS 14765. I upgraded the two existing bearing trees and added one more. The corner is tied to the following bearing trees and reference objects:

8" Black Ash S37°W 39.05 feet — 5" Spruce S31°E 10.52 feet
9" Aspen N62°E 13.25 feet — Steel Sign Post West 2.24 feet



Signed by Earl W. Applekamp

Date September 8, 1995

Surveyor's Michigan License No. 17610